

Ho

HO 57

12-14-54

Estimate to under pin

135	lin ft	4 in footer	'mths' @ .30	40.50
135	"	"	labor @ .60	81.00
19	"	step footer	'mths' @ .30	5.70
14	"	"	labor @ .60	11.40
135	lin ft	tinplate metal	@ 12 1/4	16.87
500	concrete	block	'mths' @ .28	140.00
500	"	"	labor @ .27	135.00
600	brick	for steps	'mths' @ .05	30.00
600	"	"	labor @ .06	36.00
8	Wall	Ventilator	@ \$1.50	12.00
35	Bags	Groutment	@ \$1.25	46.25
8	step	heads	'mths' @ \$3.50	28.00

Shoring

\$100.00

Hoisting (mths)

\$100.00

~~By Reg~~

782.72

Request Item #89
Paul Owen