

Inland Steel Co.

Club House

(1)	<u>Concrete</u>			
	Foundation footers	46 yds @ 10 <sup>00</sup>	46000	
	Chimney & Pier footers	15 yds "	15000	
	Basement Floor 4"	7000 ft @ 20¢	140000	
	3 Floor Slabs 2 1/2"	2100 ft @ 17¢	357000	
	Stone Fill under Basmt. Slab	60 yd. @ 2.50	15000	653000 ✓
(2)	<u>Excavation</u>			
	1700 sq yd. Hauled-		19900	
	300 " " Backfill		40000	
	Footer Excavation Lab.		9000	239000 ✓
(3)	<u>Waterproofing</u>			
	105 Gal Emulsion	@ .55	5775	
	200 yds Saturated Membrane	@ .18	3600	
	Labor		7000	
	Inside Plastered Wall. Labor.		6000	
	150 Gal. Emulsion	@ .55	8250	30625 ✓
(4)	<u>Masonry</u>			
	Fire Brick	2400 @ 105 Per M.	25200	
	Face Brick	60,000 @ 29. <sup>00</sup>	174000	
	Common Brick	55,000 @ 20. <sup>00</sup>	110000	
	Cinder Blocks	22,600	260000	
	Mortar	500 Per M.	90000	
	Brick + Block Lab		32500	
	Cleaning Brick		9000	
	Scaffold + Lab		33000	1036200 ✓
(5)	<u>Drain Tile</u>			
	500 ft @ .08		4000	
	Ditching + Laying		7500	
	20 yd Crushed Stone		5000	16500 ✓
(6)	<u>Steel</u>			
	Structural Steel	?	577500	
	Labor		131000	
	Bar Joists		499000	
	Lath + Accessories		96600	
	Fire Escape + Stairs		283900	
	toilet Partitions		49600	
	Labor		222000	
	Welding		17500	1877100 ✓
(7)	<u>Tile Work</u>			
	Ceramic + Quarry Tile		155400	
	Asphalt Tile		129200	
	Acoustic Tile (for Bowling Alley)		171400	456000 ✓
(8)	<u>Plaster</u>			
	2740 yds on Metal L.	@ 1.00	274000	
	4982 " " Sheet R.	.70	348740	622740 ✓

Contd.