

To: Guy Baker

From Amos Kinney

Estimate on building a new two stall garage replacing Garage #113 and 114. all wood construction with concrete floor and shingle roof.

14	2x4x12'	Plates	} 3100 Bdft. @ .13 = 403.00
94	2x4x10'	Studs	
44	2x6x14'	Rafters	
38	2x6x12'	Clg. Joist	
8	2x4x12'	Gable Ends	
840'	Shiplap	Sheathing	
340'	Shiplap	Partition	
Cornice Material			25.00
Vents			15.00
Roofing - 9 square @ 8.00			72.00
Nails + screws			12.00
1000 ft. Siding			210.00
Paint Exterior 2 Coats			60.00