

# Smith

## DISTRIBUTING CO.



831 E. BROADWAY • LOUISVILLE 4, KY.

7 September 1954

*Where should cooling tower be?*

*1360  
1500  
2860*

Inland Steel Company  
Wheelwright, Kentucky

Attention: Mr. L. S. Becker

Re: Wheelwright Hospital  
Air Conditioning

Dear Sir:

Enclosing your prints of hospital showing duct layout. You will note that we have shown return air from doctor's office above the ceiling, this was done to keep these offices more private. Room No. 8 (ward) will be equipped with a diffuser that can be completely cut off.

Your price of equipment F.O.B. factory is as follows:

One (1) AST-500-23 Master Matic A.C. Unit	\$ 1054.26	<i>mined.</i>
One (1) 102-W Atmospheric Cooling Tower	<i>Wood</i> 92.00	<i>\$184. metal</i>
One (1) 1 H.P. Centrifugal Pump	115.00	<i>* 97. pump</i>
One (1) 1 H.P. Allen Bradley Starter	25.00	<i>1360 -</i>
Three (3) BR-8 Carnes Ceiling Diffusers	55.00	} <i>\$180.10</i>
Four (4) BR-6 Carnes Ceiling Diffusers	64.90	
Three (3) 12x12 RL-230 Titus Return Air Registers	8.00	
Two (2) 12x12 T-700 Titus Return Air Door Grilles	15.20	
One (1) 24x12 T-700 Titus Return Air Door Grilles	12.00	
One (1) 8" Diffuser with cut-off Damper	<u>25.00</u>	
<b>TOTAL</b>	<b>\$ 1466.36</b>	

Estimated freight \$50.00.

We are unable to give you a price on prefabricated duct work that can be assembled on the job; however, we submitted your print to a local sheet metal contractor who installed the job in your general offices and they have given us the following prices.

(1) Fabricated Duct F.O.B. Louisville, Kentucky	589.60
(2) Fabricated Duct and Delivered by Fabricators Truck	743.38
(3) Fabricated Duct Delivered and Installed, Excluding Insulation, Cutting, Patching and Redecorating	1524.60