SCHEDULE OF MATERIALS.

BASEMENT

NO.	ROOM & SPACE	FLOOR	BASE	BORDER	WALLS	C'L'G.	FURRED HEIGHT	WAINS	SHELVES	REMARKS	DETAIL SHEET NO.
1	Boiler Room	Cement	___	___	Cement	Plas.	20'4"				
2	Switchboard Room	Do	___	___	See Remarks	___	___			One wall smooth tile. Others unfinished.	
3	Emerg. Generator Room	Do	___	___	Unfin.	___	___				
4	Gas Meter Rm.	Do	___	___	Unfin.	___	___				
5	Coal Bunker	Do	___	___	Unfin.	___	___				
6	Refriger. Mach. Room	Do	___	___	Unfin.	___	___				
7	Stair Hall	Do	___	___	See Remarks	___	___			Stop plas. at landing betw. base. and first floor.	
8	Toilet Room	Do	___	___	Unfin.	___	___				
9	Laundry	Cement	Cement at Int. Part.	___	Plas at Int. Part.	___	___				
10	Soiled Linen	Cement	Facing Tile	___	Facing Tile	___					
11	Doctor's Entr.	Cement	Cement	___	Plas.	Plas.	10'1"				
12	Men's Toilet	Cement	Facing Tile	___	Facing Tile	Plas.	10'1"			Non-slip terr. in shower	
13	Janitor's Clos.	Cement	___	___	Unfin.	___	___		(2)18" Metal		
14	Vestibule	Cement	Cement	___	Plas.	Plas.	10'1"				
15	Women's Toilet	Cement	Facing Tile	___	Facing Tile	Plas.	10'-1"			Non-slip terr. in shower	
16	Rest Room	Asph. Tile	Cement	___	Plas.	Plas.	Do				
17	General Shops	CEMENT	Do	___	Int. Part. Plas.	___	___				
18	Flake & Tubular Ice	Quarry Tile	Facing Tile	___	Facing Tile	Cement Plas.	10'-1"				
19	Elevator									Walls of shaft smooth-faced struct. clay tile	
20	Incinerator	Cement	Facing Tile	___	Facing Tile	___	___				
21	Clean Linen	Do	Cement	___	Plas.	Plas.	10'-1"				
22	Corridor	Cement	Cement	___	Plas.	Plas.	10'-1"				

FIRST FLOOR.

NO.	ROOM & SPACE	FLOOR	BASE	BORDER	WALLS	C'L'G.	FURRED HEIGHT	WAINS	SHELVES	REMARKS	DETAIL SHEET NO.
101	Vegetable Preparation	Quarry Tile	Quarry Tile	___	Plas.	Acoust. Tile	8-10	Tile 5'-0"			1
102	Meat Preparation	Quarry Tile	Quarry Tile		Plas.	Acoust. Tile	8-10	Tile 5'-0"			
103	Daily Stores	Terr.	Terr.		Plas.	Plas	8-10		(5) 18" Metal		
104	Main Kitchen	Quarry Tile	Quarry Tile		Plas.	Acoust. Tile	See Fl. Plans	Tile 5'0"		Note: Raised Bases & Depression	11
104_1	Dishwashing Rm.	Quarry Tile	Quarry Tile		Plas.	Acoust. Tile	8-10	Tile 5'0"		Corner guards on Ext. Corners	12
104_2	Tray Set Up & Tray Cart Str. Rm	Quarry Tile	Quarry Tile		Plas.	Acoust. Tile		Tile 5'0"		Corner guards on Ext. Corners	12
105	Stair Hall No.1	Do	Steel String.		Plas.	Plas.	See Sect.			Cement, non-slip cement treads on steel stairs	13
106	Stair Ext. Hall	Do	Do		PLAS.	PLAS.	8-10				
107	Can Washing Rm.	Cement	Facing Tile	___	Facing Tile	Plas.	8-10				
108	Special Diet Kitchen	Quarry Tile	Quarry Tile	___	Plas.	Acoust. Tile	8-10	Tile 5'-0"			
109	Dietitian's Office	Terr.	Terr.	___	Plas.	Acoust. Tile	8-10				
110	Dining Room	Terr.	Terr.	___	Plas.	Acoust. Tile	8-10	Tile 5'0"		See 110_2	
110_2	Serving Area	Quarry Tile	Quarry Tile	___	Plas.	Acoust. Tile		Tile 5'0"		Furr Plas. Bm to 7'-0" above fl. bet. serving & din.	11
111	Dining Room	Terr.	Terr.	___	Do	Do	8-10	Do		See 111_2	
111_2	Serving Area	Quarry Tile	Quarry Tile	___	Do	Do		Do		Do	11
112	Emerg. Women Toilet & Lkr. Rm	Terr.	Terr	___	Plas.	Plas.	8-10	See Remarks		Wains. 6'4" behind lavatory & around toil. comp. Furr Beams to 8'-8"	
113	Meeting Room	Asph.	Do	Terr. 13"	Plas.	Acoust. Tile	10-0				
114	Library	Do	Do	Do	Do	Do	10-0		See Detail	Furr Beams to 8'-8"	11
115	Stair Hall No.2		Steel String		Plas.	Plas.	See Sect.			Cement, non-slip cement treads on steel stairs	13
116	Central Store Rm	Cement	Cement		Plas.	Plas.	8-10		See Detail	GUARDS ON ALL WINDOWS.	
117	Receiving & Uncrating	Cement	Cement		Plas.	Plas.	8-10				11
118	Pharmacy	Terr.	Terr.		Plas.	Plas.	8-10				
119	Drug Prep. & Storage Room	Terr.	Terr.		Plas.	Plas.	8-10		See Detail		
120	Alcohol Storage Vault	Cement	Cement		Do	Do	8-10				10
121	Emerg. Operating Room	Terr.	Terr.	___	Plas.	Plas.	8-10	Tile 7'2"		Grid in Floor	
122	Utility & Bath Room	Do	Do		Do	Do	8-10	Tile 5'-0"		Grid in Floor 10" Base under tub	11
123	Supply Room	Do	Do	___	Do	Do	8-10		(5)18" Metal		
124	Toilet Room	Terr.	Terr.	___	Plas.	Plas.	8-10	Tile 4'-0"			
125	Ambulance Ent. & Waiting Rm.	Do	Do	___	Do	Do	8-10				
126	Nurses Toilet & Lkr. Room	Terr.	Terr.	___	Plas.	Plas.	8-10	See Remarks		Plumbing wall to be tiled 6'-0" high	
127	Emerg. Operating Room	Terr.	Terr.	___	Plas.	Plas.	8-10	Tile 7'-2"		Grid in floor	
128	Morgue & Autopsy	Terr.	Terr.	___	Plas.	Plas.	8-10	Tile 5'0"			
129	Body Refrigerator	Terr.	Do		Facing Tile	Mastic				Slope floor to drain to door. Walls & Clg. by Rfg. Cont.	
130	Incinerator Rm.	Terr.	Terr.		Plas.	Plas.	8-10				
131	Janitor's Closet	Cement	Cement		Cement Plas.	Cement Plas.	8-10		(2)12" Metal		
132	Shaft-Ducts, Wiring, etc.									Smooth-faced structural clay tile	
133	Elevator shafts									Smooth-faced structural clay tile	
134	Corridor	Asph.	Proj.	Terr. 13"	Plas.	Accous. Tile	8-10			Non-slip terr. mat at elev. dr.	

SUB TERR. WHERE SHOWN

SECOND FLOOR.

NO.	ROOM & SPACE	FLOOR	BASE	BORDER	WALLS	C'L'G.	FURRED HEIGHT	WAINS	SHELVES	REMARKS	DETAIL SHEET NO.
201-204	Private Rooms	Asph Tile	Terr.	Terr. 13"	Plas.	Plas.	8'10"	At Lav.	___	Proj. Base at Bed Wall	11
202	Toil. & Shower for Priv. Rm.	Terr.	Terr.	___	Plas.	Plas.	Do	Tile	___	Wains 4'0" at toilet 6'0" at shower.	11
203-205	Closets	Terr.	Terr.	___	Plas.	Plas.	Do	___	___	Raise fl. in clos. 6"	11
206	Toil. for Private Room	Terr.	Terr.	___	Plas.	Plas.	Do	Tile 4'0"	___		
207	Stair Hall, No.1	Terr.	Terr.	___	Do	Do	Do	___	___	Steel String. at Stair in Lieu of Base.	13
208	Semi-Private Rm.	Asph. Tile	Terr.	Terr. 13"	Plas.	Plas.	Do	At Lav.	___	Proj. Base at Bed Wall	11
209	Private Room	Asph. Tile	Terr.	Terr. 13"	Plas.	Plas.	Do	At Lav.	___	Do	11
210-216	Storage Closets	Do	Do	___	Do	Do	Do		(5)18" Metal		
213	Bed Pan, steril.	Terr.	Do	___	Do	Do	Do	5'0"			
211-214	Lav. & Toil.	Terr.	Terr.	___	Do	Do	Do	At Lav.	___		11
212	Patients Bath & Shower Room	Terr.	Terr. @ 4'0"	___	Plas.	Plas.	Do	Tile	___		11
215	Treatment & Exam. Room	Terr.	Terr.	___	Plas.	Plas.	Do	At Lav.	___		11
217	Toil. Rm. for Treatment Rm.	Do	Do	___	Do	Do	Do		___		
218	Unit Supply Rm.	Terr.	Terr.	___	Plas.	Plas.	Do	___	(2)18" Metal		
219	Nurses Station	Terr.	Terr.	___	Plas.	Acoust. Tile	Do	___	___	Provide Terr. Base Under Nurses Desk	10
220	Nurses Toilet Room	Do	Do	___	Do	Plas.	Do	Tile 4'0"	___		
221	Linen Room	Terr.	Terr.	___	Plas.	Plas.	Do	___	___		
222	Nourishment Kitchen	Do	Do	___	Do	Do	Do	___	___		
223	Patients Bath Room	Do	Do	___	Plas.	Plas.	Do	Tile	___	Wains 4'0". 6'-0" at tub.	
224	Ward	Asph. Tile	Terr.	Terr. 13"	Plas.	Plas.	Do	At Lav.	___	Proj. Base at Bed Wall	11
225	Semi-Private Room	Asph. Tile	Terr.	Terr. 13"	Plas.	Plas.	Do	At Lav.	___	Do	11
227	Utility Room	Terr.	Terr.	___	Plas.	Acoust. Tile	Do	Tile 5'3"	___		
228	Utility Room Soiled Section	Do	Do	___	Do	Do	Do	Do	___		
229	Stair Hall No.2	Do	Do	___	Do	Plas.	Do	___	___	Steel String. at Stair in Lieu of Base.	13
230-233 256-259	Private Rooms	Asph. Tile	Terr.	Terr. 13"	Plas.	Plas.	Do	At Lav.	___	Proj. Base at Bed Wall	11
231	Toilet Private Room	Terr.	Terr.	___	Plas.	Plas.	Do	Tile 4'0"	___		
232-234 238-240	Closets, Priv. Rooms		Terr.	Terr.	___	Do	Do	Do	___	___	Raise Floor in Closet 6"
235-237	Toil. & Shower Private Room	Terr.	Terr.	___	Plas.	Plas.	Do	Tile	___	Wains. 4'-0" at Toilet. 6'-0" at Shower	11
241	Toilet Priv. Rm.	Terr.	Terr.	___	Plas.	Plas.	Do	Tile 4'0"	___		
242-245	Semi-Priv. Rm.	Asph. Tile	Terr.	Terr. 13"	Plas.	Plas.	Do	At Lav.	___	Proj. Base at Bed Wall	11
246	Female Public Toilet	Terr.	Terr.		Plas.	Plas.	8-10	Tile 4'-0"			
247	Male Public Toilet	Terr.	Terr.		Do	Do	Do	Do			
248	Visitors Waiting Room	Asph. Tile	Terr.	Terr. 13"	Plas.	Plas.	Do				
249	Elevator shafts	___	___	___	___	___	___			Smooth-faced Struct. Clay Tile	
250	Linen	Terr.	Terr.	___	Plas.	Plas.	8'-10"	___	(5)18" Metal		
251-255	Semi-Priv. Rm.	Asph. Tile	Terr.	Terr. 13"	Plas.	Plas.	Do	At Lav.		Proj. Base at Bed Wall	11
252-253	Toilet & Shower	Terr.	Terr.	___	Plas.	Plas.	Do	Tile		Wains 4'0" at Toilet 6'-0" at Shower	
254	Sub-Utility Rm.	Terr.	Terr.	___	Plas.	Plas.	Do	Tile 5'3"			
256-257 261	Semi-Private Room	Asph. Tile	Terr.	Terr. 13"	Plas.	Plas.	Do	At Lav.		Proj. Base on Red Wall.	11
258-259	Toilet & Shower	Terr.	Terr.	___	Plas.	Plas.	Do	Tile		Wains 4'0" at Toilet. Furr Beams to 8'-8"	
260	Sub-Utility Rm.	Terr.	Terr.	___	Plas.	Plas.	Do	Tile 5'3"			
265-268 269	Semi-Private Room	Asph. Tile	Terr.	Terr. 13"	Plas.	Plas.	Do	At Lav.		Proj. Base at Bed Wall	11
262	Invinerator & Wheel Chairs	Asph. Tile	Terr.	Terr. 13"	Plas.	Plas.	Do	___			
263	Janitors Closet	Terr.	Do	___	Cement Plas.	Cement Plas.	Do	___	(2)12" Metal		
264	Pipe Shaft	___	___	___	___	___	___	___		Smooth-faced Struct. Clay Tile	
266	Sub-Utility Room	Terr.	Terr.	___	Plas.	Plas.	8'-10"	Tile 5'3"			
267	Ward	Asph. Tile	Terr.	Terr. 13"	Plas.	Plas.	Do	At Lav.		Proj. Base on Bed Wall	11
270-273	Private Room	Asph. Tile	Terr.	Terr. 13"	Do	Do	Do	At Lav.			11
271	Toilet for Private Room	Terr.	Terr.	___	Do	Do	Do	Tile 4'-0"			
272-274	Closet for Private Room	Terr.	Terr.	___	Do	Do	Do	___		Raise Fl. in closet 6"	11
275	Toilet & Shower	Terr.	Terr.	___	Plas.	Plas.	Do	Tile		Wains 4'-0" at Toilet 6'-0" at Shower	11
276-277	Corridors	Asph.	Proj. Terr.	Terr. 13"	Plas.	Acoust. Tile	Do			Non-slip Terr. Mat at The Elevator Doors.	

THIRD FLOOR.

NO.	ROOM & SPACE	FLOOR	BASE	BORDER	WALLS	C'L'G.	FURRED HEIGHT	WAINS	SHELVES	REMARKS	DETAIL SHEET NO.
301	Corridor & Scrub up Alcove	Terr.	Terr. Proj.	___	Plas.	Acoust. Tile	9'-4"	Tile AT SCRUB SINKS ONLY	___	Grid in Floor.	
302	Surg. Supervisor	Terr.	Terr.	___	Plas.	Do	Do	___	___		
303	Clean-up Room	Terr.	Terr.	___	Plas.	Plas.	Do	Tile 5'-3"	___	Grid in Floor.	
304-306	Major Operating Rooms	Terr.	Terr.	___	Plas.	Plas.	Do	Tile 7'-4"	___	Grid in Floor.	
305	Work Room	Terr.	Terr.	___	Do	Do	Do	Do	___	Grid in Floor.	
305_A	Sterilizer Equip. Room	Cement	Cement	___	Do	Do	Do	___	___		
307	Stair Hall No.1	Terr.	Terr.	___	Do	Do		___	___	Steel String. at Stair in Lieu of Base.	
308	Anesthesia Stor. Room	Terr.	Terr.	___	Plas.	Plas.	Do	___	(5)18" Metal	Grid in Floor.	
309	Cystoscopic Rm.	Terr.	Terr.	___	Plas.	Plas.	Do	Tile	___	Do	
310	Toilet Cystoscopic Room	Do	Do	___	Do	Do	Do	Tile 4'0"	___	Do	
311	Splint Closet	Terr.	Terr.	___	Plas.	Plas.	9'-4"	___	(6)18" Metal		
312	Plaster Closet	Do	Do	___	Do	Do	Do	___	(5)12" Metal		
313	Fracture Room	Terr.	Terr.	___	Plas.	Plas.	Do	Tile	___	Grid in Floor.	
314	Doctors Shower Room	Do	Do	___	Do	Do	Do	Tile 6'-0"	___	Non-slip Terr. Fl.	
315	Doctors Toilet	Do	Do	___	Do	Do	Do	Tile 4'-0"	___		
316	Doctors Lkr. Rm.	Do	Do	___	Do	Do	Do	___	___	Furr in Heads of Lkrs.	
317	Dark Room Cystoscopic	Terr.	Terr.	___	Plas.	Plas.	Do	___	___		
318	Nurses Station	Do	Do	___	Do	Acoust. Tile	Do	___	___	Provide Terr. Base Under Nurses Desk	
319	Nurses Toilet Room	Do	Do	___	Do	Plas.	Do	Tile 4'0"	___		
320	Linen Room	Do	Do	___	Do	Do	Do	___	___		
321	Nourishment Kitchen	Do	Do	___	Do	Do	Do	___	___		
322	Patients Bath-Room	Terr.	Terr.	___	Plas.	Plas.	Do	Tile	___	Wains 4'-0". 6'-0" at Tub.	
323	Ward	Asph. Tile	Terr.	Terr. 13"	Do	Do	Do	At Lav.	___	Proj. Base at Bed Wall.	11
324	Semi-Private Room	Do	Do	Do	Do	Do	Do	Do	___	Do	
326	Utility Room	Terr.	Terr.	___	Plas.	Acoust. Tile	Do	Tile 5'-3"	___		
327	Utility Room Soiled Section	Do	Do	___	Do	Do	Do	Do	___		
328	Stair Hall No.2	Do	Do	___	Do	Plas.	___	___	___	Steel String. at Stairs in Lieu of Base.	
329-333 335-340	Private Room	Asph. Tile	Terr.	Terr. 13"	Plas.	Plas.	9'-4"	At Lav.	___	Proj. Base at Bed Wall.	11
330-339	Toil., Priv. Rm.	Terr.	Do	___	Do	Do	Do	Tile 4'-0"	___		
331-332 337-338	Closet, Private Rooms	Terr.	Terr.	___	Do	Do	Do	___	___	Raise Floor in Closet 6".	11
334-336	Toilet & Shower, Private Room	Do	Do	___	Do	Do	Do	Tile	___	Wains 4'0" at Toilet 6'-0" at Shower.	
341-342 343-344	Semi-Private Rooms	Asph. Tile	Terr.	Terr. 13"	Plas.	Plas.	Do	At Lav.	___	Proj. Base at Bed Wall.	11
345	Womens Public Toilet Room	Terr.	Terr.	___	Do	Do	Do	Tile 4'-0"	___		
346	Mens Public Toilet Room	Do	Do	___	Do	Do	Do	___	___		
347	Visitors Waiting Room	Asph. Tile	Terr.	Terr. 13"	Do	Do	Do	___	___		
348	Elevator Shaft	___	___	___	___	___	___	___	___	Wall of Shaft Smooth-faced Struct. Clay Tile.	
349-355	Wards	Asph. Tile	Terr.	Terr. 13"	Plas.	Plas.	9'-4"	At Lav.	___	Proj. Base at Bed Wall.	11
350-356	Semi-Priv. Rms.	Do	Do	Do	Do	Do	Do	At Lav.	___	Proj. Base at Bed Wall.	
351	Formulae Room	Terr.	Terr.	___	Plas.	Plas.	Do	Tile 5'3"	___		
352	Bottle Wash Room	Terr.	Terr.	___	Plas.	Plas.	Do	Tile 5'3"	___		
353	Utility Room Soiled Section	Terr.	Terr.	___	Do	Acoust. Tile	Do	Do	___		
354	Utility Room	Do	Do	___	Do	Do	Do	Do	___		
357	Incinerator	Terr.	Terr.	___	Plas.	Plas.	Do	___	___		
358	Janitor's Closet	Terr.	Terr.	___	Cement Plas.	Cement Plas.	Do	___	(2)12" Metal		
358_A	Janitor's Closet	Terr.	Terr.	___	Cement Plas.	Cement Plas.	9'-4"	___	___		
359	Pipe Shaft	___	___	___	___	___	___	___	___	Smooth Faced Struct. Clay Tile	
360	Central Supply Work & Receiv. Rm.	Terr.	Terr.	___	Plas.	Plas.	9'-4"	Tile	___	Tile Wains 7'-4" at Front of Sterilizer Wall Only.	
360_A	Sterilizer Room	Cement	Cement	___	Do	Do	Do	___	___		
361	Sterile Supply Room	Terr.	Terr.	___	Do	Do	Do	___	___		
362	Nurses Toilet	Terr.	Terr.	___	Plas.	Plas.	Do	Tile 4'-0"	___		
363	Nurses Shower Rm.	Do	Do	___	Do	Do	Do	Tile 6'-0"	___	Terr., Non-slip Fl. in Shower	
364	Nurses Locker Rm.	Terr.	Terr.	___	Plas.	Plas.	Do	___	___	Furr-in Heads of Lkrs.	
365	Corridors	Do	Terr. Proj.	___	Do	Acous. Tile	Do	___	___	Grid in Floor.	
366	Corridors	ASPHALT	Do	TERR.	Do	Do	Do	___	___	TERR. NON SLIP MAT AT ELEVATORS	

STERILIZER SCHEDULE

S-1 Bulk Supply Sterilizer, pressure.

S-2 Small Supply Sterilizer, pressure.

S-3 ~~Hot Air Sterilizer, Electric.~~ Not used.

S-4 Utensil Sterilizer, non-pressure.

S-5 ~~Instrument Sterilizer, Electric.~~ Not used.

S-6 Water Still.

S-7 Instrument Sterilizer, Electric.

S-10 ~~Laboratory Autoclave, double-wall pressure.~~ Not used.

S-11 Instrument Washer-Sterilizer, pressure.

S-12 Instrument Washer-Sterilizer, pressure.

S-13 Water Sterilizer, 15 gals., pair.

S-14 Hot Air Sterilizer, Electric.

S-16 Instrument Sterilizer, Electric.

S-17 Pasteurizer & Bottle Sterilizer.

There are no fixtures bearing the numbers, 8,9,15.

LAUNDRY. EQUIPMENT SCHEDULE.

L-1 Cascade Washer 42" x 54".

L-2 Cascade Washer 36" x 18".

L-3 Extractor 30".

L-4 Starch Cooker 75 gal.

L-5 Soap Tank.

L-6 Flat Work Ironer 120".

L-7 Tumbler.

L-8 Ironing Board.

L-9 Press 63".

L-10 Press 31".

L-11 Table 3'-0" x 11'-0". Gr. 2

L-12 Bleach Crooks (By Owner)

L-13 Truck Tubs. Gp. 2

L-14 Air Compressor.

PLUMBING FIXTURE SCHEDULE.

P-1 Water Closet.

P-2 Lavatory.

P-3 Lavatory with elbow control handles.

P-4 Patients' Bath

P-5 Shower, with curtain rod.

P-6 Urinal.

P-7 Janitor's Receptor.

P-8 Disposal Sink.

P-9 Bed Pan Washer-Sterilizer.

P-10 Fittings for Medicine Sink.

P-11 Scrub-up Sink, with knee control stirrup.

P-12 Surgical Soap Dispenser. Gr. 2

P-13 Utility Sink.

P-14 Drinking Fountain.

P-20 Bed Pan Rack.

P-24 Water Closet with BedPan Cleanser.

P-26 Fittings for Bottle Washer Sink.

P-27 Fittings for Cabinet Sink in Formulae Room.

P-29 Equipment for Cleanup Sink.

P-30 Utensil Sink.

P-31 Instrument & Scrub Sink, with knee control stirrup.

P-32 Utility Sink.

P-33 Suction Bottle Unit.

P-34 Plaster Sink, with knee control valve.

P-35 Developing Tank.

P-36 Clean-Up Sink.

P-41 Autopsy Table.

P-44 Utensil Sink, with elbow control handles.

P-45 Patients' Bath & Shower.

P-46 Developing Tank.

P-47 Service Sink.

P-48 Drinking Fountain.

P-49 Drinking Fountain, Boiler Room & Laundry.

P-50 Laundry Tray.

P-51 Oxygen Outlet.

P-52 Boiler Room Sink.

NOTE: There are no fixtures bearing the numbers, 15,16,17,18,19,21,22,23,25,28,37,38,39,40,42,43.

P-53 Cystoscopic Sink.

P-54 Dark Room Sink.

P-55 Large Pharmacy Sink.

P-56 Pharmacy Counter Sink.

P-57 Ice Sink.

KITCHEN EQUIPMENT SCHEDULE.

K-1 Soiled dish counter.

K-2 Soiled dish counter.

K-2-1 Soiled glass counter.

K-2-2 Clean glass shelf.

K-3 Clean dish counter.

K-4 Dish Washer.

K-5 Glass Washer.

K-6 Pre-Wash Sink.

K-7 Coffee Urn.

K-7-1 Coffee Urn Stand.

K-8 Electric Toaster, Gr. 2

K-9 Electric griddle, Gr. 2

K-10 Cook's refrigerator.

K-11 Tray setup counter & Plate warmer.

K-12 Tray Carts, Gr. 2

K-13 Refrigerator by owner.

K-14 Hot plate by owner.

K-14a Hot plate by owner.

K-15 Ice cream cabinet.

K-16 Salad & Dessert Counter.

K-16-1 Cold pan section.

K-17 Cook's table and Serving Counter.

K-17-1 Steam table.

K-17-2 Bainmarie.

K-17-3 Cook's sink.

K-17-4 Pot rack.

K-18 Broiler.

K-19 Range.

K-19-1 Spacer.

K-20 Range.

K-20-1 Spacer.

K-21 Fryer.

K-22 Hour. Kit. Unit.

K-23 Baker's Table.

K-24 Bake Oven.

K-25 Pan Rack.

K-26 Steamer.

K-27 Kettles.

K-28 Mixer.

K-29 Work Table.

K-30 Work Table.

K-31 Sink.

K-32 Pot sink.

K-33 Work Table.

K-34 Refrigerator.

K-35 Small Range.

K-36 Base Counter.

K-37 Pantry Sink.

K-38 Vegetable Sink.

K-39 Peeler.

K-40 Meat Block.

K-41 Meat Sink.

K-42 Table. (Shelf)

K-43 Food Cutter. Gr. 2

K-44 Table.

K-45 Meat Slicer. Gr. 2

K-46 Cafeteria Counter.

K-46-1 Tray and Silver Section.

K-46-1A Tray and Silver Section.

K-46-2 Steam Table Section.

K-46-3 Cold Pan Section.

K-46-4 Water Station.

K-46-5 Coffee Urn Section.

K-46-6 Tray Rail.

K-46-7 Guard rail.

K-46-7A Guard rail.

K-47 Coffee Urn.

K-48 Ice Cream Cabinet.

K-49 Salad Refrigerator.

K-50 Work Counter.

K-51 Ice Maker.

K-52 Flake Ice Machine.

K-53 Ice Storage Cabinet.

K-54 Bread Box.

K-55 Silver Bins.

K-56 Pot Cabinet

K-57 Garbage Can Washer.

NOTE: Items marked "By Owner" and "Gr. 2" on entire sheet not in this contract.

ALTERATIONS & ADDITIONS
BOWLING GREEN-WARREN COUNTY HOSPITAL
BOWLING GREEN, KENTUCKY.

ROBERT W. McMEEKIN, ARCHITECT
LEXINGTON, KENTUCKY
SAMUEL HANNAFORD & SON
CONSULTING ARCHITECTS, CINCINNATI, O.

DATE: NOV. 2, 1949
DRAWN BY: J. INGEL
REVISIONS
3-4-50

ROBERT W. McMEEKIN REGISTERED No. 37 COMMONWEALTH OF KENTUCKY ARCHITECT

SHEET NO. 9 OF 25 SHEETS